



NOTES

1. SOURCE CABLE WILL BE OF SUFFICIENT LENGTH TO REACH U.C.E.M.C. TRANSFORMER AND ALLOW 6'-0" ADDITIONAL FOR CONNECTION.
2. GFCI WILL BE REQUIRED ON ALL TEMPORARY CONSTRUCTION ENTRANCES. ALL CIRCUITS FROM SWITCH BOX ON POLE TO CONSTRUCTION SITE WILL BE OF APPROVED TYPE CABLE AND KEPT IN A GOOD, SAFE, SERVICEABLE CONDITION.
3. CONTRACTOR WILL PULL THE INSTALLED GROUND ROD OR DRIVE IT 18" UNDER THE GROUND WHEN SERVICE IS DISCONNECTED.
4. APPROVED 60 AMP WEATHERPROOF SWITCH BOX.
5. NO. 6 CU. OR NO. 4 AL. SOURCE WIRES. MUST BE N.E.C. APPROVED FOR DIRECT BURIAL.